

NOVA BLOCK™ 6

CRAWLSPACE VAPOR BARRIER

NovaBlock is a line of high-performance, woven-reinforced membranes made from virgin resin and designed to protect against moisture and soil gas intrusion. NovaBlock 6 is a high-strength, 6 mil thick membrane ideal for reliable vapor intrusion protection.



FEATURES & BENEFITS

- ASTM E84 Class A Fire Rated
- No VOC/Odors
- ASTM E1745 Class A: Highest performance for plastic water vapor barrier
- Woven reinforced
- Superior puncture and tear resistance
- Light weight and easy to handle

6 MIL MEMBRANE FOR RELIABLE VAPOR INTRUSION PROTECTION.

©2026 IPG® • NovaBlock 6 • 110226

800-565-2000 | ecp.itape.com

PRODUCT ATTRIBUTES

CHARACTERISTICS	TEST METHOD	NovaBlock™ 6
Thickness mil (mm)	ASTM D1777	6 mil (152 mm)
Weight	N/A	4.1 oz/yd^2 (139 g/m^2) ± 5%
Roll Sizes	N/A	Standard sizes: 4 ft x 200 ft and 12 ft x 100 ft Custom sizes are available upon request
Folded	N/A	V or C folded options available
Weave	N/A	Woven clear HDPE scrim
Coating	N/A	LDPE, 1.5 mil average on each side (35 g/m^2/side)
Color	N/A	White, black or colored coatings available
Temperature Range	N/A	-76°F to 158°F (- 60°C to 70°C)
Strip Tensile (New material)	ASTM D5035	MD 105 lb/in (910 N/5cm) TD 90 lb/in (780 N/5cm)
Tongue Tear (Large scale)	ASTM D5884	MD 50 lb/in (222 N) TD 50 lb/in (222 N)
Grab Tensile	ASTM D7004	MD 95 lb/in (422 N) TD 120 lb/in (533 N)
Trapezoidal Tear	ASTM D4533	MD 40 lb/in (178 N) TD 30 lb/in (133 N)
Mullen Burst	ASTM D751	215 psi (1482 kPa)

PRODUCT APPLICATIONS

- Crawlspaces encapsulations
- Radon mitigations
- Underslab
- Moisture control
- Vapor intrusion projects

INSTALLATION

- Crawlspace Installation

NovaBlock should be installed over the entire floor area and no more than 3" from the top of foundation wall. All seams should be overlapped a minimum of 12 inches and taped with NovaBlock Seam Tape. Terminate NovaBlock to foundation walls using NovaBlock Foundation Tape, approved mechanical fasteners and construction sealants.

- Under-Slab Installation

NovaBlock should be installed over the entire floor area of aggregate, sand or earth base. All seams should be overlapped a minimum of 6 inches and taped with NovaBlock Seam Tape. All penetrations should be sealed using NovaBlock, NovaBlock Seam Tape, NovaBlock Foundation Tape, or approved sealants.

